

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/OW/WORK_INDENT16947

APPROVED SCHEDULE - B


Tender Notification EE/BTP/BBMP/E-PMT/10/2014-15, Date: 21.2.2015


Name of Work: Providing Rain Water charging Pits at Defence Layout, MSPalya, Ramachandrapura and Gangamma Gudi areas in Ward No. 11, Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				S VENKATESHAPPA	
				In Figures	In Words
1	131.42	Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	264.0	Rupees Two Hundred Sixty Four Only
2	99	Laying reinforced cement concrete pipe NP4 / prestressed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets complete as per specifications, A.1000 mm dia, etc., complete and as per the directions of the Engineer-in-charge of the work	M	11800.0	Rupees Eleven Thousand Eight Hundred Only
3	15.55	Providing and filling in foundation with granite / trap broken metal 100mm, and down size, with approved sand including had packing, ramming, watering, including cost of all materials and labour with all lead and lift, etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	1962.0	Rupees One Thousand Nine Hundred Sixty Two Only
4	186.63	Supply and Providing Aggregate 53 mm nominal size etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	670.0	Rupees Six Hundred Seventy Only
5	15.55	Supply and Providing Aggregate 40 mm and below etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	670.0	Rupees Six Hundred Seventy Only
6	15.55	Supply and Providing Aggregate 20 mm and below etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	900.0	Rupees Nine Hundred Only
7	15.55	Supply and Providing Sand etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	1300.0	Rupees One Thousand Three Hundred Only



8	2.59	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplasticiser @ 3lts confirming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, curing, etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	5900.0	Rupees Five Thousand Nine Hundred Only
9	1.56	Providing mild steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery etc., complete and as per the directions of the Engineer-in-charge of the work	Qtl	7975.0	Rupees Seven Thousand Nine Hundred Seventy Five Only
10	131.42	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means including loading and unloading. From 0.00 to 2.00 Km etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	70.0	Rupees Seventy Only


Signature of the Contractor


Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92